



Government of Rajasthan
Office of Project Director

Rajasthan Urban Infrastructure Development Project

AVS Building, Jawahar Circle, JLN Marg, Jaipur - 302017

Tel No.: +91 141 2721966, Fax No.: +91 141 2721919 email : mail@ruidp.gov.in, web site : www.ruidp.gov.in

No.F3(106)(11)(2)/PMU/RUSDIP/KARAULI/WW/2009/8338 Date: 26/06/2011
608358

M/s

Sub: Clarification-4 to the query raised by Bidders during pre bid meeting
Ref: Bid No. RUSDIP/NCB/ IR 31/ 31813 dated 28.02.11

Dear Sir,

The clarification to the query raised under package No RUSDIP/TR-03/KRL/WW 02(Lot 2) for "Design, construction, supply, erection testing, commissioning and first five years operation & maintenance of sewage treatment plant 5 MLD near charagah & sewage pumping station including all civil, electrical, mechanical, pumping and other allied works at Karauli town." is hereby enclosed. This clarification is as per Clause 7 of Sec-I; Instructions to Bidders of Bid Document.

Now no further queries shall be entertained.

Encl: - Clarification to the
Bidder's Query

Yours sincerely

Addl. Project Director

Date: 26/06/2011

No.F3(106)(11)(2)/PMU/RUSDIP/KARAULI/WW/2009/8338

Copy to following for information :-

1. PA to Project Director, RUIDP
2. Additional Project Director, RUIDP
3. Financial Advisor, RUIDP
4. Chief Engineer (T), RUIDP, Jaipur
5. SE, Zone-Jaipur, RUIDP, Jaipur
6. Team Leader, IPMC, RUIDP, Jaipur
7. Team Leader, DSC, RUIDP, Jaipur
8. Executive Engineer, IPUI, Karauli
9. M/s


Heaven
Superintending Engineer (WW)

Design, construction, supply, erection testing, commissioning and first five years operation & maintenance of sewage treatment plant 5 MLD near charagah & sewage pumping station including all civil, electrical, mechanical, pumping and other allied works at Karauli town. (On Item Rate Basis) under RUSDIP/ TR-03/KRL/WW/02(Lot 2)


Clarification - 4

Queries raised by M/s Dolphin Aqua Cure Pvt. Ltd.

Sr. No.	Query	Reference	Reply
1	From where will the electric connection be taken. How far will be the HT line from the SPS 1, SPS 4 and STP site. This is required to measure the exact amount of HT cable required to give power connection to these points.	Section VI, Page No. VI-141	Distance of three phase electric line passing approximately at 500m, 500m and 300m from SPS-1, SPS-2 and STP respectively.
2	Do we need HT meters or LT metering shall be done.	Section VI, Page VI-152	Electronic microprocessor based (static) meter shall be provided in a separate HT metering panel.
3	During the visit of the site it was noted by us that the exact pipeline in the mela gate route is 150 m more than mentioned quantity. The prices asked by you are lump sum. How will you make payment of excess quantity.	Section VI, Page No. VI-10	Length mentioned in the bid is correct. Bid conditions prevail.


Team Leader, 28/5/11
DSC I


Team Leader
IPMC


SE (WW)
IPMU